ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Dated 26th November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., of 22nd December 1930, for Restoring Petekere Minor Tank Register No. 2 of Kankanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. (*a*) Tenders quoting percentages above or below estimate will be rejected.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Restoring Petekere Minor Tank Register No. 2 of Kankanhalli Taluk" in default of which tenders will be rejected.

5. The final acceptance of tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted against each item of work both in words and figures.

Restoring Petekere Minor Tank Register No. 2 of Kankanhalli Taluk.

Serial No.	Items of work	Per	Quantity	Rate
	Bund R. L. 55'00 top width 4 feet.			Rs. a. p
1	Clearing jungle and cutting grips, etc.	Grade	22	
2	Earthwork to bund with watering and tamping, complete	C.yds.	1,939	
3	Turfing front and rear slopes	S.yds.	3,247	
4	New stone revetment work	C.yds.	100	
5	Old stonework with new jelly	"	25	
6	Providing new grade stones with numbering and painting.	Each	33	
7	Index stones with numbering and painting ...	"	22	
8	Register No. stone do	"	1	
9	B. M. stones do	"	2	
10	Gauge stone do	"	1	
	Total Bund	...	...	
	Anne.			
1	Earthwork for foundation	C.yds.	17	
2	Concrete in surki mortar	C.ft.	1,539	
3	Burnt stone in surki mortar	"	589	
4	Pointing with surki mortar	S.yds.	3·22	
5	Burnt stone slabs 6" thick	S.ft.	156	
6	Rough stone work new	C.yds.	47	
7	New jelly wedging forapron	"	33	
8	Clearing jungle	Lump	sum	
	Total ...	...	...	
	Widening and deepening the feeder channel of Petekere.			
1	Earthwork yet remaining to be done ...	C.yds.	6,025	